

Material Summary w/Kits (Grouped)

Job: 2022-18 (STENTO)

Page 1 of 4
August 19 2025

Material	Total	Total + Waste	Cost
{s}MATERIAL NOT ASSIGNED	5 pieces	5 pieces	\$0.00
MATERIAL NOT ASSIGNED			
			<hr/> \$0.00

Banding

Material	Total	Total + Waste	Cost
Paint Grade EB	210.10 ft.	210.10 ft.	\$0.00
Paint Grade Edgebanding			
			<hr/> \$0.00

Blum Hinge Plates

Material	Total	Total + Waste	Cost
Blum 0mm BH175H7100	62 pieces	62 pieces	\$97.96
Blum 0mm BH175H7100			
			<hr/> \$97.96

Blum Hinges

Material	Total	Total + Waste	Cost
Blum 110	8 pieces	8 pieces	\$14.80
			<hr/> \$14.80

Blum TANDEM

Material	Total	Total + Waste	Cost
563H2290B10	4 pair	4 pair	\$144.00
Blum Tandem 563H2290B10			
563H4570B	2 pair	2 pair	\$72.00
Blum Tandem 563H4570B			
563H5330B	22 pair	22 pair	\$792.00
Blum Tandem 563H5330B			
			<hr/> \$1,008.00

A list of all material required for the job grouped by Material Manager grouping, giving a cost sub-total for each group, sorted alphabetically. Displays kitted parts.

Board Stock

Material	Total	Total + Waste	Cost
1 1/8" Soft Maple	9.63 bd. ft	9.63 bd. ft	\$69.78
Soft Maple			
1 Maple natural lumber	86.25 bd. ft	86.25 bd. ft	\$0.00
Maple natural			
1" Soft Maple	186.55 bd. ft	186.55 bd. ft	\$0.00
Soft Maple			
2 3/4 Maple	2.63 bd. ft	3.42 bd. ft	\$40.99
Maple			
3/4 Solid Maple	1.08 bd. ft	1.08 bd. ft	\$6.46
Maple			
5/8 Solid Maple	64.67 bd. ft	64.67 bd. ft	\$388.01
Maple			
			<hr/> \$505.24

Glass

Material	Total	Total + Waste	Cost
1/8 Glass	27.69 sq. ft	27.69 sq. ft	\$0.00
Glass			
			<hr/> \$0.00

Hinges

Material	Total	Total + Waste	Cost
Stento Inset Hinge	54 pieces	54 pieces	\$0.00
Concealed			
			<hr/> \$0.00

Panel Stock

Material	Total	Total + Waste	Cost
1/2 Prefinished Ply	1.89 sheets	2.18 sheets	\$163.25
Prefinished Ply			
1/4 Paint Grade Ply	3.19 sheets	3.67 sheets	\$0.00
Paint Grade Ply			

A list of all material required for the job grouped by Material Manager grouping, giving a cost sub-total for each group, sorted alphabetically. Displays kitted parts.

1/4 Prefinished Ply	9.29 sheets	10.68 sheets	\$405.95
Prefinished Ply			
3/4 Birch Ply Shop	1.48 sheets	1.70 sheets	\$202.20
Birch Ply			
3/4 Oak MDF	0.14 sheets	0.17 sheets	\$0.00
Oak/MDF Core			
3/4 Paint Grade Ply	9.81 sheets	11.28 sheets	\$924.93
Paint Grade Ply			
3/4 Prefin Maple 2S ply core	23.41 sheets	26.92 sheets	\$1,614.96
Prefin Maple			
PI-05 / Wh 4x10	1.16 sheets	1.16 sheets	\$69.54
Prelam w/ White Backer			

\$3,380.84

Pulls & Knobs

Material	Total	Total + Waste	Cost
Knob #1	1 pieces	1 pieces	\$0.00
1 1/4 in Round Knob			
Mockett DP156 - Black	19 pieces	19 pieces	\$0.00
DP156			

\$0.00

Screws

Material	Total	Total + Waste	Cost
Drawer Guide Screws	176 pieces	176 pieces	\$5.28
08 X 7/16 #2 PH-TRUSS			
Sample Screw	124 pieces	124 pieces	\$29.76
#4 2 X 1 1/2 lkjdsf			

\$35.04

Solid Surface Matl

Material	Total	Total + Waste	Cost
SS1 2" Stone	1.38 sheets	1.38 sheets	\$0.00
SS1			

A list of all material required for the job grouped by Material Manager grouping, giving a cost sub-total for each group, sorted alphabetically. Displays kitted parts.

\$0.00

Spacer Blocks

Material	Total	Total + Waste	Cost
Blum T59.3570 Spacer Block	8 pieces	8 pieces	\$0.00
Blum T59.3570 Rollout Spacer Block			
			\$0.00

Molding Profiles

Material	Total	Total + Waste	Cost
Stento Base Shoe (3/4 Solid Maple)	17.33 ft.	17.33 ft.	\$104.00
Stento UC Scotia (3/4 Solid Maple)	45.29 ft.	45.29 ft.	\$271.73
Stento Base w/ shoe (3/4 Solid Maple)	3.67 ft.	3.67 ft.	\$22.00
Stento Scotia Combo (3/4 Solid Maple)	64.29 ft.	64.29 ft.	\$385.74
Stento 5 Crown (3/4 Solid Maple)	36.10 ft.	36.10 ft.	\$216.63
Stento Crown Fascia (3/4 Solid Maple)	35.69 ft.	35.69 ft.	\$214.13
Batten 502 1/4 x 3/4 (3/4 Solid Maple)	7.74 ft.	7.74 ft.	\$46.41
Casing 120 11/16 x 3 1/2 (3/4 Solid Maple)	3.52 ft.	3.52 ft.	\$21.10
Casing 121 11/16 x 4 1/2 (3/4 Solid Maple)	40.52 ft.	40.52 ft.	\$243.14
Stento CR #1 (3/4 Solid Maple)	13.33 ft.	13.33 ft.	\$79.97
Stento Base #1 (3/4 Solid Maple)	10.80 ft.	10.80 ft.	\$64.81
Stento CA (3/4 Solid Maple)	14.33 ft.	14.33 ft.	\$86.00
Stento Base Shoe (3/4 Solid Maple)	7.33 ft.	7.33 ft.	\$44.01
Stento Betsy (3/4 Solid Maple)	13.88 ft.	13.88 ft.	\$83.25
Sub-total:			\$1,882.91
Total:			\$6,924.78

A list of all material required for the job grouped by Material Manager grouping, giving a cost sub-total for each group, sorted alphabetically. Displays kitted parts.